

Schedule of Rate

Name of Work: Stainless steel railing work at newly constructed ramp for the physically challenged students NIT Silchar.

Location: Entry from Old Classroom, Old Library Building, RPC center, Physic Department

Completion period: 15 days.

OR:

CR:

OM:

Sl. No.	Description of Item	Unit	Quantity	Rate in fig	Rate in word	Amount
1	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-incharge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).	Kg	320.00			

Total = Rs.